OFFICIAL BIDDING DOCUMENT

Telecommunications Technology Solutions Inc. (TelTech)

Corporate Tender Secretariat · Procurement & Network Engineering Division

RFP-TELTECH-FWA-2026-001 / APPENDIX B
Author: OLIVER TUNGOL
Date: October 14, 2026

Commercial Proposal & Bill of Quantities (BoQ) Templates

Turnkey Equipment Pricing, Turnkey Rollout Services & Vendor Financing Framework

DOCUMENT NUMBER	AUTHOR	TARGET SPECTRUM	BIDDING STATUS
RFP-TELTECH-FWA-2026-001	OLIVER TUNGOL	Band n50 (1.5 GHz, 60 MHz TDD)	Official Request for Proposal

Instructions to Bidders: Complete all unit rates in USD ($) and Philippine Pesos (PHP ₱ at baseline FX 55.00) using the official Excel BoQ file (`06_RFP_Commercial_Price_Book_and_BoQ_Template.xlsx`). All prices must be firm, fixed, and valid for 180 days.

TABLE 1: LOT 1 — RAN HARDWARE & ACCESS EQUIPMENT (PER SITE BASIS)

ITEM REF	EQUIPMENT DESCRIPTION	TECHNICAL SIZING / MODEL	QTY PER SITE	UNIT PRICE (USD) [BIDDER TO QUOTE]	TOTAL PRICE PER SITE (USD)	REMARKS / BIDDER MODEL
RAN-HW-01	5G Baseband Unit (BBU)	19" subrack, dual -48V DC PSU, 4x 25G backhaul, 6x 25G eCPRI	1 set	*[Bidder Quote]*	*[Formula = Qty * Rate]*	Specify model & datasheet
RAN-HW-02	8T8R Remote Radio Unit (RRU)	Band n50 (1.5 GHz), 60 MHz IBW, 8x40W (320W total RF power)	3 sets	*[Bidder Quote]*	*[Formula = Qty * Rate]*	3 Sectors per site
RAN-HW-03	Macro High-Gain Antennas	8-port cross-pol, 17.5 dBi gain, AISG 2.0 internal eRET	3 sets	*[Bidder Quote]*	*[Formula = Qty * Rate]*	Or integrated AAU option
RAN-HW-04	RF Jumpers & Optical Patchcords	High-grade armored optical fiber, weatherproof boots, grounding kits	1 lot	*[Bidder Quote]*	*[Formula = Qty * Rate]*	All accessories included
RAN-HW-05	BBU Base Software & 5G Features	Band n50 carrier license, MU-MIMO, beamforming, sleep-mode energy saving	1 lot	*[Bidder Quote]*	*[Formula = Qty * Rate]*	Perpetual base software
SUBTOTAL	BTS Equipment Package per Site	*(BBU x1, 8T8R RRU x3, Antennas x3, SW)*	1 Site	—	*[Sum of Items HW-01 to HW-05]*	*Total BTS Hardware*

TABLE 2: LOT 1 — RAN TURNKEY ROLLOUT SERVICES (PER SITE BASIS)

ITEM REF	SERVICE DESCRIPTION	SCOPE OF WORK	QTY PER SITE	UNIT PRICE (USD) [BIDDER TO QUOTE]	REMARKS / METHODOLOGY
RAN-SVC-01	Site Survey, Engineering & TSSR	Tower audit, structural verification, drone LOS photo sweep, civil sketch	1 site	*[Bidder Quote]*	Field survey report delivery
RAN-SVC-02	Project Management & Mobilization	Dedicated rollout PMO, site acquisition coordination, milestone tracking	1 site	*[Bidder Quote]*	Dedicated PM team

ITEM REF	SERVICE DESCRIPTION	SCOPE OF WORK	QTY PER SITE	UNIT PRICE (USD) [BIDDER TO QUOTE]	REMARKS / METHODOLOGY
RAN-SVC-03	**Installation & Commissioning (I&C)**	Rigging, antenna mounting, cable routing, BBU wiring, initial power-up	1 site	*[Bidder Quote]*	Civil and telecom I&C
RAN-SVC-04	**Single Site Optimization (SSO/SSV)**	Station testing, sector drive test, throughput call, ping, handover test	1 site	*[Bidder Quote]*	SSV acceptance sign-off
RAN-SVC-05	**Cluster Optimization Services**	Cluster tuning, inter-site interference, tilt adjustments (per site share)	1 site	*[Bidder Quote]*	Cluster drive testing
RAN-SVC-06	**Central Warehousing & Logistics**	Staging, asset tagging, kitting, indoor climate storage	1 site	*[Bidder Quote]*	Inventory management
RAN-SVC-07	**Delivery & Basic Hauling to Site**	Regional hauling, rough-road 4x4 transport to rural barangay location	1 site	*[Bidder Quote]*	Complete site delivery
SUBTOTAL	**RAN Turnkey Services per Site**	*Full Turnkey Rollout & Commissioning Services*	**1 Site**	***[Sum of Items SVC-01 to SVC-07]***	*Total Turnkey Services*

> **Total Day-1 RAN Capex per Site (Equipment + Turnkey Services):** `[Sum of Hardware + Turnkey Services]`
> **Phase 1 Program Total (1,000 Sites):** `[Total per Site * 1,000]`

TABLE 3: LOT 2 — POWER SYSTEMS & PASSIVE INFRASTRUCTURE

ITEM REF	SYSTEM DESCRIPTION	TECHNICAL SIZING	APPLICATION	UNIT PRICE (USD) [BIDDER QUOTE]	UNIT PRICE (PHP @ 55 FX)
PWR-EQ-01	**12.0 kW Modular DC Rectifier Plant**	19" 3U subrack, 4 x 3.0 kW modules (N+1), SMPS controller	Co-loc / Greenfield	*[Bidder Quote]*	*[Formula = USD * 55]*
PWR-EQ-02	**48V LiFePO4 Battery Bank**	High-cycle LFP with smart BMS, sized for >= 12.0 kWh usable energy over 4.0h @ 3.0 kW load, <= 80% DoD, 80% SoH (min >= 20.0 kWh nominal installed bank capacity, min 400 Ah @ 48V, loss-based calculation)	Co-loc / Greenfield	*[Bidder Quote]*	*[Formula = USD * 55]*
PWR-EQ-03	**TowerCo DC Tap-Off & Metering Kit**	DC tap enclosure, revenue Class 1.0 kWh meter, SPD Type 2	Leased TowerCo	*[Bidder Quote]*	*[Formula = USD * 55]*
PWR-EQ-04	**15 kVA Diesel Generator Set**	Soundproof canopy, 500L–1000L tank, ATS, auto-start	Greenfield (Class T4)	*[Bidder Quote]*	*[Formula = USD * 55]*
CIV-EQ-01	**30m Monopole Tower & Foundation**	Galvanized steel monopole, pile/pad foundation, compound fence	Greenfield (Class T4)	*[Bidder Quote]*	*[Formula = USD * 55]*
CIV-EQ-02	**Grounding Grid & Lightning System**	Copper earth ring, Cadweld, ground rods, air terminal (<= 5 Ohms)	Greenfield (Class T4)	*[Bidder Quote]*	*[Formula = USD * 55]*

TABLE 4: LOT 3 — 5G CORE NETWORK (5GC SA) & DATACENTER

ITEM REF	SUBSYSTEM COMPONENT	DIMENSIONING / SIZING	MODEL TYPE	TOTAL YEAR 1 PRICE (USD) [BIDDER QUOTE]
5GC-HW-01	**Compute Server Nodes (2U)**	Dual Xeon Gold / EPYC, 512GB RAM, NVMe (Dual Sites, N+1)	Hardware Purchase	*[Bidder Quote]*
5GC-HW-02	**High-Throughput UPF Nodes**	80 Gbps line-rate forwarding per node with DPDK (N+1 per DC)	Hardware Purchase	*[Bidder Quote]*
5GC-HW-03	**Datacenter Network Fabric**	Spine/leaf switches (100GE / 25GE), perimeter firewalls, anti-DDoS	Hardware Purchase	*[Bidder Quote]*
5GC-HW-04	**Storage Array & Backup System**	High-IOPS redundant enterprise NVMe storage arrays	Hardware Purchase	*[Bidder Quote]*
5GC-SW-01	**5GC Control Plane Software (1M)**	AMF, SMF, PCF, UDM, UDR, AUSF, NRF, NSSF, CHF (1,000,000 Subs)	Perpetual License	*[Bidder Quote]*
5GC-SW-02	**Carrier-Grade NAT & DPI Software**	CG-NAT deterministic port license + Layer-7 DPI bandwidth policing	Perpetual License	*[Bidder Quote]*
5GC-SW-03	**CaaS / Kubernetes Orchestration**	Enterprise Kubernetes platform & container management	Perpetual / Annual	*[Bidder Quote]*
5GC-SVC-01	**Integration, IOT with RAN & UAT**	End-to-end design, commissioning, RAN interoperability testing	Professional Services	*[Bidder Quote]*
SUBTOTAL	**5G Core Year 1 Turnkey Package**	*Dual Datacenter Active-Active Setup (1M Subs)*	**Turnkey Initial**	***[Sum of Items 5GC-01 to SVC-01]***

Incremental Capacity Expansion License (Tiers above 1,000,000 Subscribers):

* *Subscribers 1,000,001 to 2,000,000:* [Bidder to Quote USD] per registered subscriber.
* *Subscribers 2,000,001 to 3,000,000:* [Bidder to Quote USD] per registered subscriber.
* *Annual Software Maintenance & Support (AMC):* [Bidder to Quote] % per annum.

TABLE 5: LOT 4 — DIGITAL OSS/BSS & FIELD FORCE AUTOMATION

ITEM REF	OSS/BSS FUNCTIONAL MODULE	DETAILED FUNCTIONAL SCOPE	LICENSE TYPE	TOTAL YEAR 1 PRICE (USD) [BIDDER QUOTE]
BSS-01	**Converged CRM & Product Catalog**	Omnichannel customer onboarding, product catalog (4 FWA tariffs)	Perpetual / Enterprise	*[Bidder Quote]*
BSS-02	**Real-Time Balance & Rating Engine**	CHF adapter, real-time prepaid quota metering, zero-balance redirect	Perpetual License	*[Bidder Quote]*
BSS-03	**Payment Channel Integration**	Native API integrations: GCash, Maya, 7-Eleven CLiQQ, Bayad Center	Integration Module	*[Bidder Quote]*
BSS-04	**Billing & Invoicing Engine**	Postpaid billing engine for SME and enterprise anchor tenants	Perpetual License	*[Bidder Quote]*
OSS-01	**Field Force Management (FMS)**	Algorithmic automated dispatch handling 3,500 daily work orders	Enterprise License	*[Bidder Quote]*
OSS-02	**Mobile Technician Android App**	Barcode scan, GPS dispatch, live RF RSRP/SINR validation tool	Unlimited Users	*[Bidder Quote]*
OSS-03	**CPE Warehouse Logistics & Reverse WMS**	Serialized asset lifecycle tracking, repossession & refurbishment module	Enterprise License	*[Bidder Quote]*
OSS-04	**Network Performance & Fault OSS**	Multi-vendor RAN/Core EMS integration, alarm correlation, RCA	Enterprise License	*[Bidder Quote]*
OSS-05	**Regulatory BI & NTC Dashboard**	Automated QoS speed compliance reporting to NTC	Included	*[Bidder Quote]*
OSS-SVC	**Systems Integration & UAT Launch**	End-to-end configuration, test scripts, launch support	Professional Services	*[Bidder Quote]*

ITEM REF	OSS/BSS FUNCTIONAL MODULE	DETAILED FUNCTIONAL SCOPE	LICENSE TYPE	TOTAL YEAR 1 PRICE (USD) [BIDDER QUOTE]
SUBTOTAL	OSS/BSS Turnkey Year 1 Package	*Full Stack Suite Dimensioned for 1M Subscribers*	Turnkey Initial	*[Sum of Items BSS-01 to OSS-SVC]*

TABLE 6: LOT 5 — SITE ACQUISITION, DETAILED SITE SURVEY (TSSR), RF DESIGN & CIVIL WORKS

ITEM REF	SERVICE / WORKS DESCRIPTION	DETAILED TECHNICAL SCOPE & DELIVERABLES	APPLICATION	UNIT PRICE (USD) [BIDDER QUOTE]	UNIT PRICE (PHP @ 55 FX)	REMARKS / METHODOLOGY
CIV-SVC-01	**Detailed Site Survey Report (TSSR)**	Structural load audit, 360° drone sweep, power/grounding audit, civil sketch, PE sign-off	All Sites (Co-loc & Green)	*[Bidder Quote]*	*[Formula = USD * 55]*	Comprehensive TSSR
CIV-SVC-02	**Site Acquisition & Permitting Support**	LGU building permits, Barangay clearances, CAAP height clearance, environmental docs	Greenfield Sites	*[Bidder Quote]*	*[Formula = USD * 55]*	Full permit clearance
CIV-SVC-03	**Equipment Pad Foundation & Cable Gantry**	Concrete plinth for DC power/battery cabinet, elevated cable ladder, AC interconnect tap	Leased TowerCo Sites	*[Bidder Quote]*	*[Formula = USD * 55]*	Co-location upgrade
CIV-SVC-04	**Greenfield Compound Works & Pad**	8m x 8m compound grading, chain-link security fence, crushed gravel, equipment pad	Greenfield (Class T4)	*[Bidder Quote]*	*[Formula = USD * 55]*	Civil compound construction
CIV-SVC-05	**Grounding Grid & Lightning Protection**	Exothermic Cadweld copper ring, ground rods, busbar, air terminal (<= 5.0 Ohms)	All Sites (Co-loc & Green)	*[Bidder Quote]*	*[Formula = USD * 55]*	Electrical grounding
CIV-SVC-06	**30m Monopole Tower Supply & Erection**	ASTM A572 steel monopole, 250 km/h wind survival, fall arrest ladder, PE certification	Greenfield (Class T4)	*[Bidder Quote]*	*[Formula = USD * 55]*	Tower supply & erection
CIV-SVC-07	**40m Monopole Tower Supply & Erection**	ASTM A572 steel monopole, 250 km/h wind survival, climbing ladder, structural sign-off	Greenfield (Terrain Opt)	*[Bidder Quote]*	*[Formula = USD * 55]*	High-clearance monopole
CIV-SVC-08	**RF Propagation Modeling & Siting**	3D ray-tracing simulation, clutter calibration, search ring generation, nominal plan	Macro Footprint	*[Bidder Quote]*	*[Formula = USD * 55]*	RF engineering model
CIV-SVC-09	**Cluster RF Optimization & Drive Test**	Multi-site cluster drive testing, antenna tilt/azimuth optimization, neighbor tuning	Per Site Share	*[Bidder Quote]*	*[Formula = USD * 55]*	Cluster optimization
TOTAL	**Lot 5 Civil & Siting Scope per Site**	*Full Turnkey Site Acquisition, Survey, Design & Civil Construction*	**Per Site Evaluated**	***[Sum of Items SVC-01 to SVC-09]***	***[Formula = USD * 55]***	*Total Lot 5 Turnkey Scope*

TABLE 7: LOT 6 — MANAGED SERVICES & 24/7 NETWORK OPERATIONS (ANNUAL OPEX)

ITEM REF	MANAGED OPERATIONS DOMAIN	SCOPE OF SERVICES	PRICING BASIS	MONTHLY RATE (PHP) [BIDDER QUOTE]	MONTHLY RATE (USD @ 55 FX)	ANNUAL COST / SITE (USD)
MS-OP-01	**24/7 Tier-2/Tier-3 Central NOC**	Active surveillance, incident triage, vendor escalation	Per Site / Month	*[Bidder Quote]*	*[PHP / 55]*	*[Monthly USD * 12]*
MS-OP-02	**Field First Line Maintenance (FLM)**	24/7 nationwide emergency restoration, MTTR <= 2-4 hrs	Per Site / Month	*[Bidder Quote]*	*[PHP / 55]*	*[Monthly USD * 12]*
MS-OP-03	**Scheduled Preventive Maintenance**	Quarterly site inspection, power, battery, grounding	Per Site / Month	*[Bidder Quote]*	*[PHP / 55]*	*[Monthly USD * 12]*
MS-OP-04	**Spare Parts Logistics & Warehousing**	Regional buffer stock, NBD replacement delivery	Per Site / Month	*[Bidder Quote]*	*[PHP / 55]*	*[Monthly USD * 12]*
MS-OP-05	**Continuous Network RF Optimization**	Routine KPI monitoring, neighbor tuning, interference mgmt	Per Site / Month	*[Bidder Quote]*	*[PHP / 55]*	*[Monthly USD * 12]*
TOTAL	**Active Network O&M Fee**	*All inclusive active telecom managed operations*	**Per Site / Month**	***[Sum of OP-01 to OP-05]***	***[Sum of USD]***	***[Annual Total USD]***

TABLE 8: LOT 7 — 5G CUSTOMER PREMISES EQUIPMENT (CPE)

ITEM REF	DEVICE DESCRIPTION	MINIMUM TECHNICAL SPECIFICATIONS	TARGET QTY (PHASE 1)	UNIT PRICE (USD) [BIDDER TO QUOTE]	TOTAL PHASE 1 COST (USD)
CPE-01	**Indoor 5G High-Gain FWA Router**	Band n50 native, >= 8.0 dBi internal antenna, Wi-Fi 6 AX1800/AX3000, 1x 2.5GE + 2x 1GE ports, TR-069/TR-369	350,000 units	*[Bidder Quote]*	*[Formula = Qty * Rate]*
CPE-02	**Outdoor 5G High-Gain FWA Package**	Band n50, IP67 enclosure, >= 12.0 dBi directional antenna, 1x 2.5GE PoE, bundled indoor Wi-Fi 6 router & PoE injector	15,000 units	*[Bidder Quote]*	*[Formula = Qty * Rate]*
CPE-SVC	**Staging, Pre-Config & SIM-Locking**	Custom firmware flashing, operator APN & PLMN lock, retail packaging for all Phase 1 terminals	365,000 units	*[Bidder Quote]*	*[Formula = Qty * Rate]*
TOTAL	**Lot 7 5G CPE Terminals Package**	*Total Initial Terminal Supply & Staging (365,000 Total Devices)*	**365,000 Units**	—	***[Sum of Items CPE-01 to CPE-SVC]***

TABLE 9: MANDATORY VENDOR FINANCING FACILITY (FORM D)

The Bidder must submit a formal, legally binding financing term sheet with the following parameters:

FINANCING LEVER	OPERATOR MANDATORY REQUIREMENT	BIDDER BINDING OFFER [BIDDER TO COMPLETE]
Financing Structure	OEM-backed Buyer's Credit or Export Credit Agency (ECA) facility	*[Bidder to Specify Facility Structure]*
Financing Quantum	Minimum **80% of Eligible Capital Expenditure** (Lots 1, 3, Turnkey Services)	*[Bidder to State % Financed]*
Equity Downpayment	Maximum **20% Downpayment** upon contract signing	*[Bidder to State Downpayment %]*
Facility Tenor	Flexible facility tenor up to **20 Years** (minimum 4 Years, 5+ Years Preferred)	*[Bidder to State Tenor in Months]*

FINANCING LEVER	OPERATOR MANDATORY REQUIREMENT	BIDDER BINDING OFFER [BIDDER TO COMPLETE]
Principal Grace Period	Deferred principal repayment / grace period up to **10 Years** (minimum 12 Months, 18+ Months Preferred)	*[Bidder to State Grace Period]*
Indicative Interest Rate	Fixed commercial rate (preferred <= 6.50% p.a.) or competitive benchmark to SOFR + spread	*[Bidder to State Fixed Rate or Spread]*
Security / Collateral	Pledge on network equipment assets without restrictive operational covenants	*[Bidder to Specify Security Terms]*
Repayment Frequency	Semi-annual or quarterly principal and interest amortizations	*[Bidder to Specify Payment Cadence]*

(End of Appendix B — Commercial Proposal & Pricing Templates)