TELECOMMUNICATIONS TECHNOLOGY SOLUTIONS INCORPORATED (TELTECH)

NATIONWIDE 5G STANDALONE (SA) FIXED WIRELESS ACCESS (FWA) NETWORK

RFP REFERENCE: RFP-TELTECH-FWA-2026-001

BID BULLETIN NO. 2.1: COMPREHENSIVE TECHNICAL, OPERATIONAL & COMMERCIAL ADDENDUM

TO ALL PROSPECTIVE BIDDERS: All Qualified Bidders, System Integrators, and Authorized Equipment Manufacturers

FROM: Oliver Tungol, Lead Technical Architect & Tender Secretariat

DATE OF ISSUANCE: October 30, 2026 (Revised & Consolidated Addendum)

SUBJECT: Technical Baseline Revisions, Mandatory RF Conformance Directives (RAN-21), and Promulgation of Consolidated 100-Question Clarifications Master

> **GOVERNING LEGAL DIRECTIVE:** This **Bid Bulletin No. 2.1** is formally promulgated pursuant to Section 1.5 (*Clarification and Amendment of Bidding Documents*) of the Master RFP Document. It updates, refines, and consolidates the directives of Bulletin 2.0. The provisions, technical standards, mandatory RF conformance testing protocols (RAN-21), and commercial rules articulated herein are seamlessly codified as binding contractual addenda to Documents 01 through 09. Prospective bidders must formulate their final 3-envelope submissions strictly in conformance with these unified engineering policies.

1. EXECUTIVE SUMMARY & TENDER STATUS OVERVIEW

Following detailed technical reviews, preliminary engineering evaluations, and structural harmonization across the 5,000 candidate barangays, TelTech officially issues this comprehensive policy bulletin (Revision 2.1). This

document codifies authoritative directives across nine (9) strategic technical domains:

1. **Cloud-Native 5G SA Core Dimensioning & User Plane Throughput (Lot 3)**
2. **Spectrum Allocation (NTC MC 006-11-2025), Band n50 Operating Passband, RF Conformance Testing (RAN-21) & Demarcation Optics (Lot 1 & Lot 6)**
3. **Customer Premises Equipment (CPE) Phased Rollout & Lifecycle Reverse Logistics (Lot 7)**
4. **Civil Works, Monopole Structural Standards & Site Power Infrastructure (Lots 2 & 5)**
5. **Operational SLAs, Radio Network KPIs & SSV Acceptance Standards (Document 04 / Appendix C)**
6. **Digital OSS/BSS, Field Force Automation & VAS Subsystems (Lot 4)**
7. **Candidate Siting Schedule Precision & Geographic Asset Provenance (Document 07)**
8. **Commercial BoQ Harmonization, Multi-Year O&M & 10-Year TCO Rules (Document 06)**
9. **Consolidated Response Matrix (Part 3: Inquiries Q045 – Q100 & Publication of 100-Question Master Register in Document 09)**

Digital OSS/BSS, Field Force Automation & VAS Subsystems (Lot 4)

Candidate Siting Schedule Precision & Geographic Asset Provenance (Document 07)

Commercial BoQ Harmonization, Multi-Year O&M & 10-Year TCO Rules (Document 06)

---

2. CLOUD-NATIVE 5G CORE (5GC SA) & DATA CENTER ARCHITECTURE (LOT 3)

2.1 User Plane Throughput Capacity Dimensioning

1. **Phase 1 Capacity Baseline (1,000,000 Subscribers):**
   - The cloud-native 5G SA Core User Plane Function (UPF) cluster must be physically and logically dimensioned to deliver an initial aggregated user-plane throughput floor of **300 Gbit/s to 500 Gbit/s**.
   - Dimensioning derives from an initial target of 300,000 concurrently active broadband households exhibiting an Average Busy-Hour Throughput (ABHT) of 1.5 Mbit/s to 2.0 Mbit/s per active subscriber at a standard 15% to 20% busy-hour concurrency factor.
2. **Expansion Horizon (3,000,000 Subscribers):**
   - The proposed containerized 5G Core Network Functions (CNF) running on Kubernetes / bare-metal server infrastructure must natively support horizontal auto-scaling of distributed UPF instances up to an aggregated user-plane throughput capacity of **1.5 Tbit/s**.
   - Expansion to 1.5 Tbit/s must be executable via software license expansion and incremental server node deployment without requiring architectural redesign, control plane migration (AMF/SMF/UDM), or database re-sharding.

3. RADIO ACCESS NETWORK (RAN), BAND n50 SPECTRUM & TRANSMISSION (LOTS 1 & 6)

3.1 Spectrum Physics, Operational Channel Window, RF Testing & Emission Suppression

1. **Active Operational Passband & Numerology:**
   - Under the National Telecommunications Commission (NTC) regulatory framework for dedicated broadband wireless communications, the authorized operational Band n50 carrier is established as **1457.0 MHz to 1517.0 MHz**, providing a single contiguous **60.0 MHz TDD channel bandwidth** centered at **1487.0 MHz** (aligned on the standard 100 kHz 3GPP RF reference raster).
   - The carrier operates at 30 kHz Subcarrier Spacing (SCS, μ=1), dimensioned for **162 Physical Resource Blocks (PRBs)** occupying 58.32 MHz active transmission bandwidth.
   - **Spectral Efficiency Comparison:** A single 60.0 MHz carrier provides 162 PRBs (97.2% frequency utilization), capturing +5.9% higher usable capacity and eliminating inter-carrier guard band waste and Carrier Aggregation (CA) overhead compared to 3x 20 MHz (153 PRBs total, 91.8% utilization).
2. **Guardband Allocation & Satellite Protection (> 1517.0 MHz):**
   - A dedicated **1.0 MHz external guardband (1517.0 MHz to 1518.0 MHz)** is allocated immediately adjacent to the upper band edge below the NTC allocation ceiling (1518.0 MHz).
   - Incorporating the internal 3GPP channel guardband of 840 kHz, the effective physical separation from the outermost active subcarrier (1516.16 MHz) to the sensitive satellite downlink boundary (1518.0 MHz) is **1.84 MHz**.
   - All gNodeB transceivers must implement sharp digital filtering ensuring out-of-band emissions (OOBE) into the adjacent maritime mobile-satellite service band (1518.0 – 1525.0 MHz) do not exceed **-30 dBm/MHz** at the antenna connector, strictly compliant with **ITU-R M.2159-0 / WRC-15 Resolution 223** and **3GPP TS 38.104 Category B**.
3. **Lower Out-of-Band Emission Limits (1432.0–1457.0 MHz):**
   - Radiated and conducted unwanted emissions in the adjacent 1432.0–1457.0 MHz block (allocated for Non-Public Networks / NPN under NTC MC 006-11-2025) must strictly meet **3GPP TS 38.104 Category B** standards with an Adjacent Channel Leakage Ratio (**ACLR ≥ 45 dB**).
4. **In-Band Broadcasting-Satellite Service (BSS) Coexistence (1452.0–1492.0 MHz):**
   - In accordance with Section IV of NTC MC No. 006-11-2025, gNodeB macro deployments overlapping the 1452.0–1492.0 MHz primary BSS allocation must support remote power control, electrical downtilt adjustments (eRET), and interference coordination to avoid detrimental interference to licensed satellite earth stations.
5. **Mandatory 3GPP TS 38.104 & TS 38.141 RF Conformance Testing Deliverables:**

- Shortlisted RAN bidders are formally required to submit certified third-party or OEM factory laboratory test reports under **3GPP TS 38.141-1 (Conducted)** and **TS 38.141-2 (Radiated)** demonstrating:
  - **Spectrum Emission Mask (SEM):** Full compliance operating at maximum rated transmitter power (+55 dBm / 320 W conducted per 8T8R sector).
  - **Adjacent Channel Leakage Ratio (ACLR):** Measured at full load (162 PRBs active).
  - **Operating Band Unwanted Emissions (OBUE):** High-resolution spectral emission mask plots across the critical **1517.0 – 1559.0 MHz** range (specifically proving the ≤ -30 dBm/MHz limit above 1518.0 MHz).
  - **Spurious Emissions:** Measured conducted unwanted emissions outside the operating band.
  - **Power De-Rating & Filtering Declaration:** If power back-off or an optional external high-Q cavity bandpass filter is required to satisfy emissions at the 1518.0 MHz boundary, the bidder must explicitly declare the exact de-rating (in dB) and quantify its impact on cell-edge link budget coverage.

6. **NTC Memorandum Circular No. 006-11-2025 & Spectrum Expansion Clarification:**
   - **Regulatory Allocation Framework:** The National Telecommunications Commission (NTC) has promulgated NTC Memorandum Circular No. 006-11-2025 governing International Mobile Telecommunications (IMT) spectrum in the 1427.0–1518.0 MHz (1.5 GHz L-Band) frequency range:
     - **1427.0 – 1457.0 MHz (30 MHz):** Allocated for **Non-Public Networks (NPN)** / dedicated private wireless networks.
     - **1457.0 – 1518.0 MHz (61 MHz):** Allocated for **Public Networks (PN)**, formally confirming the regulatory foundation for TelTech's authorized 1457.0–1517.0 MHz (60 MHz continuous TDD) active operational carrier.
   - **Regulatory Consultations on Spectrum Expansion:** The Operator is actively conducting regulatory and technical consultations with the NTC to clarify mechanisms for expanding operational spectrum bandwidth beyond the 60 MHz baseline (up to 80 MHz channel operation). Specifically, TelTech is clarifying whether supplemental operational access or secondary co-channel/adjacent-channel usage may be authorized, particularly across suburban, provincial, and rural clusters where:
     1. No Non-Public Networks (NPN) are licensed or physically operating within the 1427.0–1457.0 MHz block; and/or
     2. Incumbent mobile network operators (Globe Telecom, Smart Communications) are not actively utilizing the L-Band / Band n75 as Supplemental Downlink (SDL).
   - **Technical Bidding Implications (Hardware & Software):**
     - **Hardware Wideband Native Capability:** All proposed 5G NR Baseband Units (BBU), Remote Radio Units (RRU) / Active Antenna Units (AAU), and Customer Premises Equipment (CPE) RF front-ends must natively support the full 3GPP Band n50 tuning range (**1432.0 – 1517.0 MHz, 85 MHz Instantaneous Bandwidth / IBW**) in hardware.
     - **Software Reconfigurability:** Should the NTC grant supplemental operational bandwidth or regional secondary channels, systems must support software/firmware reconfiguration (e.g., expanding from 60 MHz to 80 MHz channel bandwidth or activating carrier aggregation) remotely without requiring physical antenna swaps, hardware replacements, or tower truck rolls.

3.2 Baseband Architecture & Form Factor Preferences

1. **Form Factor Preference for Co-Location (897 Sites):**
   - Outdoor blade Baseband Units (blade BBUs) featuring zero ground-footprint pole/wall mounting are strongly preferred across all 897 tower co-location sites. Blade architectures minimize TowerCo compound lease fees and accelerate deployment velocity. Compact outdoor cabinet BBUs are permitted only where indoor shelter space is pre-contracted.
2. **Site Transport Capacity & Optical Transceiver Boundary:**
   - Initial gNodeB backhaul throughput dimensioning of **1 Gbit/s** per site is approved for Day 1 traffic modeling.
   - However, backhaul interfaces must support hardware upgradeability to **10 Gbit/s** via standard SFP+ optical cages.
   - **Demarcation Supply Scope:** The RAN contractor shall supply dual-rate **10GE/25GE eCPRI/Ethernet adaptive optical modules** (1310nm Single-Mode Fiber, LC duplex, 10 km reach) for all BBU optical ports. TelTech shall provide compatible optical transceivers on the transmission demarcation router/switch ports.
   - **Configuration Boundaries:** The RAN contractor executes all BBU port IP address provisioning, VLAN tagging, QoS DSCP priority mapping, and IEEE 1588v2 PTP / SyncE frequency/phase synchronization. TelTech transmission teams configure transport tunneling (MPLS-VPN / SRv6).

3.3 Nearest Tower Geographic Coordinates & Siting Inventory Precision (Document 07)

1. **Candidate Siting Geographic Precision:**
   - In response to technical simulation requirements, high-precision WGS84 geographic coordinates (6 decimal places) for all nearest co-location towers have been populated in Document 07 (`07_RFP_5G_FWA_Candidate_Site_List_and_Rollout_Schedule.xlsx`) across Tab 'All 5,000 Sites' and Batch 1 through Batch 5.
   - All 60 previously flagged reversed coordinate entries have been fully verified and corrected against audited telecom asset databases.
   - Bidders are reminded that tower coordinate data constitute confidential operator assets provided under the RFP Non-Disclosure Agreement (NDA) solely for RF propagation modeling, link budget simulations, and construction feasibility assessment.

---

4. CUSTOMER PREMISES EQUIPMENT (CPE) ROLLOUT & LIFECYCLE REVERSE LOGISTICS (LOT 7)

4.1 Phased Hardware Delivery Model

1. **Initial Phase 1 Form Factor:**
    - Recognizing commercial manufacturing timelines for Band n50 outdoor units, TelTech authorizes a phased rollout: Bidders are permitted to supply high-gain 5G Indoor Units (IDU, minimum 8.0–10.0 dBi equivalent antenna gain with integrated 4x4 MIMO and external TS-9/SMA antenna ports) for initial Phase 1 residential deployments.
2. **Outdoor Unit (ODU) Commitment:**
    - Bidders must concurrently submit a firm, contractually committed product delivery roadmap for high-gain Outdoor Units (ODU, $\ge$ 12.0 dBi directional gain, IP67 weather-proofing, pole-mountable) within **6 to 9 months** following contract award.

4.2 CPE Warranty vs. Churned Reverse Logistics Lifecycle

1. **Manufacturer Warranty (Defect Liability Period):**
    - All supplied CPE hardware carries a mandatory **24-month (2-year) free replacement warranty** covering internal hardware defects, component burnout, and manufacturing faults.
2. **Churned CPE Recovery Rate ($\ge$ 70%):**
    - The contractual $\ge$ 70% recovery target applies exclusively to **reverse logistics operations executed by field force personnel** retrieving TelTech-owned CPE units from churned or canceled subscriber premises.
    - Recovered units undergo factory diagnostic testing, firmware re-flashing, cosmetic refurbishment, and re-packaging into active forward deployment inventory.
    - Hardware damage resulting from proven subscriber vandalism, fire, or force majeure is excluded from warranty and replenished via the Master Rate Card spare parts schedule.

---

5. CIVIL, STRUCTURAL & SITE POWER INFRASTRUCTURE (LOTS 2 & 5)

5.1 Class T4 Greenfield Monopoles (103 Sites)

1. **Structural Wind Load Standards:**
    - All newly built Class T4 Greenfield Monopoles must be structurally engineered in compliance with the **National Structural Code of the Philippines (NSCP 2015, 7th Edition) / EIA/TIA-222-G**.
    - Structures must withstand extreme typhoon wind gusts of **270 km/h (Zone 2) up to 315 km/h (Zone 1)** under full design dead load:
    - 6x 5G Remote Radio Units (RRUs);
    - 1x Active Antenna Unit (AAU) or 3x directional passive panel antennas;
    - Up to **1.2 m² total projected windward surface area** for microwave backhaul antennas (equivalent to 1x 1.2m or 2x 0.6m high-wind parabolic dishes);

- Associated cable ladders, feeder runs, and top lightning protection rod.

2. **Foundation Hydrological Elevation:**
   - **Standard Non-Flood Soils:** Reinforced concrete equipment plinths shall have an elevation of **300 mm (0.30 m)** above finished grade level.
   - **Documented Flood Zones (50-Year Inundation History):** Civil contractors shall construct elevated structural steel equipment platforms raised **1.0 m to 1.5 m** above finished grade level, priced pursuant to the approved Master Rate Card.
3. **Starlink Satellite Backhaul Mounting Interface:**
   - Where hybrid LEO satellite backhaul is designated, contractors shall install a hot-dip galvanized mounting mast (minimum 60 mm / 2.375-inch outer diameter, 2.5 mm wall thickness) with an unobstructed view of the sky. For ground sites, a dedicated gantry standoff arm is utilized; for tower sites, a rigid leg standoff clamp is installed.

5.2 AC Electrical Utility Interconnection & Standby Power

1. **Service Entrance Capacity:**
   - AC service drops shall be sized for **100A, 230V single-phase (or 3-phase where commercially available)**.
   - The contractor's civil/electrical scope includes installation of the weatherhead, service mast, utility-grade meter base, manual transfer switch (MTS), and main AC distribution board with Class I+II Surge Protective Devices (SPD). Utility energization and power billing accounts are administered directly by TelTech.
2. **Site Power Rectifier Architecture (Lot 2):**
   - Each site requires one (1) high-efficiency outdoor-rated rectifier system with N+1 modular switchmode rectifier redundancy (e.g. 3x 50A modules providing 100A continuous N+1 DC output). Remote SNMPv3 / Modbus-TCP telemetry reporting into the centralized OSS is mandatory.
3. **Diesel Generator Fuel at Commissioning:**
   - Contractors are responsible for supplying diesel fuel strictly for generator commissioning and full-load burn-in testing (minimum 4 hours continuous run). Routine fuel replenishment transitions to TelTech O&M upon Provisional Acceptance (PAC).

5.3 Technical Site Survey Reports (TSSR) & Drone Sweeps

1. **Panoramic Photographic Standards:**
   - For tower co-location sites (Class T1–T3), contractors shall perform 360° panoramic photographic sweeps at antenna centerline height (and 20m, 30m, 40m AGL) using calibrated drone photographic platforms.
   - In areas where drone operations are legally prohibited by aviation authorities (CAAP restricted airspace, airport buffer zones, military reservations) or severe inclement weather, high-resolution manual panoramic photography captured by certified tower riggers from the tower climbing platform is accepted.

6. OPERATIONAL SLAS, RADIO NETWORK KPIS & SSV ACCEPTANCE (APPENDIX C)

6.1 Radio Performance Indicators (Nationwide 24/7/366)

To harmonize rigorous carrier-grade service quality with real-world FWA wireless propagation environments, the following SLA thresholds are formally enacted:

1. **Call / Session Setup Success Rate (CSSR):**
   - **Target Standard: 97.0%** (revised from 99.0%)
   - **Minimum Threshold: 96.0%** (revised from 97.5%)
   - Formula: $\text{CSSR} = \text{RRC Setup Success Rate} \times \text{5G QoS Flow Setup Success Rate} \times 100\%$
2. **Call Drop Rate (CDR):**
   - **Target Standard: $\le$ 1.5%** (revised from $\le$ 0.5%)
   - **Maximum Threshold: $\le$ 2.0%** (revised from $\le$ 1.0%)
3. **Packet Loss Rate:**
   - Evaluated at the **PDCP (Packet Data Convergence Protocol) Layer** pursuant to 3GPP TS 38.314.
   - **Target Standard: $\le$ 0.10%**; **Maximum Threshold: $\le$ 0.20%**.
4. **Time-Consistent Busy Hour (TCBH):**
   - Evaluated on a per-cell basis as the rolling continuous 60-minute window demonstrating highest combined uplink/downlink traffic volume over a 30-day observation period.

6.2 Service Credit Assessment & Stabilization Governance

1. **Financial Penalty Floor:**
   - Service Credit liquidated damages are assessed **exclusively when monthly performance breaches the Minimum Threshold floor** (or exceeds the Maximum Threshold for CDR/Packet Loss). Performance falling between the Target Standard and Minimum Threshold mandates engineering root-cause analysis and corrective cluster optimization without financial penalty.
2. **Post-PAC Cluster Stabilization Window:**
   - A **90-day stabilization grace period** is granted for each site rollout cluster commencing from Provisional Acceptance (PAC), during which financial Service Credits for Network Availability (NAV) and MTTR are suspended while operational baselines and field spares logistics are stabilized.
3. **OSS Throughput Counters vs. Contractual SLAs:**
   - Financial penalties shall not be assessed against instantaneous OSS cell-edge throughput counters due to dependencies on subscriber traffic distribution and concurrency. Cell-edge speed compliance is governed by Single Site Verification (SSV) and cluster drive acceptance.

6.3 Single Site Verification (SSV) Speed Criteria by RSRP Brackets

Single Site Verification stationary throughput benchmarks for a 60 MHz Band n50 channel under a standard 8:2 (DDDDDDDSUU) or 7:3 TDD frame configuration are established as follows:

- **Near Zone (RSRP $\ge$ -80 dBm):** Downlink $\ge$ 200 Mbit/s | Uplink $\ge$ 25 Mbit/s
- **Mid Zone (-95 dBm $\le$ RSRP < -80 dBm):** Downlink $\ge$ 100 Mbit/s | Uplink $\ge$ 10 Mbit/s
- **Cell Edge Zone (-105 dBm $\le$ RSRP < -95 dBm):** Downlink $\ge$ 35 Mbit/s | Uplink $\ge$ 5 Mbit/s

(Note: A 5 Mbit/s uplink floor is mandatory to guarantee TCP ACK throughput and interactive voice/video responsiveness).

6.4 Field Installation & Maintenance Metrics

1. **Subscriber Installation Scope:**
    - Encompasses on-site RF signal verification, optimal wall/roof/pole mounting, outdoor weather-sealed Cat6 cabling (up to 30m), PoE injection, indoor Wi-Fi router setup, zero-touch provisioning via FMS app, and verified speed test sign-off.
2. **First-Time-Right (FTR) Installation Rate ($\ge$ 95%):**
    - Calculated monthly as:

$$\text{FTR Rate} = \left(\frac{N_{\text{completed installations}} - N_{\text{repeat visits within 14 days}}}{N_{\text{completed installations}}} \right) \times 100\%$$

- Any physical revisit required within fourteen (14) calendar days following sign-off due to workmanship defects, misaligned antennas, or provisioning errors is classified as a failed FTR event.

1. **Spare Parts Management Service (SPMS) NBD Delivery:**
    - Next Business Day (NBD) replacement requires dispatch and physical delivery of replacement spare modules to the **designated regional forward maintenance depot / TelTech regional maintenance center** within the next business day (Monday through Saturday, cut-off 15:00) following RMA notification.

---

7. DIGITAL OSS/BSS, FIELD FORCE AUTOMATION & VAS INTEGRATION (LOT 4)

1. **Native Automated Business Intelligence (BI):**
    - The BSS/OSS suite must incorporate an integrated reporting engine providing scheduled generation of operational, billing, subscriber churn, and SLA compliance reports in CSV, Excel, and PDF formats. Furthermore, open database views / secure REST APIs must be exposed for data pipeline ingestion into TelTech's enterprise data lake.
2. **Cloud Contact Center Integration (CCaaS):**

- The BSS/CRM platform must expose standard TM Forum Open APIs (**TMF621 Customer Management, TMF622 Product Ordering, TMF632 Party Management**) for single-pane CTI screen-pops, automated customer verification, and unified ticketing integration with TelTech's cloud contact center.

3. **Value-Added Services (VAS) & SMS Gateway Connectivity:**
   - The BSS must provide native **SMPP v3.4 and RESTful SMS gateway adapters** to trigger automated customer notifications (one-time passwords [OTP], billing invoices, payment acknowledgments, and service notifications). TelTech provides the SMS gateway termination service.
4. **Field Force Management (FMS) Mobile Application Capabilities:**
   - **Navigation:** Deep-linking or redirecting from within the FMS app to standard third-party navigation applications (Google Maps, Waze) for routing to site/subscriber coordinates is fully approved.
   - **Electronic Signatures:** Capturing touchscreen handwritten customer signatures on the mobile application upon job completion satisfies formal proof-of-delivery. Third-party digital certificate authorities (PKI/CA) are not required for residential installation orders.
   - **RF Signal Logging:** Certified mobile RF verification tools (e.g. Cellular-Z, G-NetTrack, Nemo Handy, or OEM diagnostic suites) are approved for logging RSRP, RSRQ, SINR, and Cell ID parameters into completion reports.
   - **Automated Service Provisioning:** Work orders successfully validated and signed off on the FMS app must automatically trigger real-time subscriber service activation in the BSS/OSS.
5. **Software SLA Boundary vs. Field Managed Services Scope:**
   - Standalone OSS/BSS software SLAs (Lot 4) govern application availability ($\ge$ 99.95%), transaction processing latency, and API throughput. Field execution metrics (Dispatch Lead Times, FTR Installation Rates, Churned CPE Recoveries) apply strictly to the Managed Services & Field Operations scope (Lot 5 / Appendix E) when awarded.

---

8. COMMERCIAL PROPOSAL, 10-YEAR TCO & PROCUREMENT GOVERNANCE (DOCUMENT 06)

1. **Total Pricing Scope (5,000 Candidate Sites):**
   - Commercial proposals must provide firm, fixed unit rates and total pricing based on the complete **5,000 candidate site scope** (Lot 1 through Lot 7). Project deployment shall proceed under the multi-batch rollout roadmap (Phase 1: 1,000 sites; Batches 2–5: 1,000 sites each).
2. **Currency Conversion Benchmark:**
   - For bid evaluation and financial modeling, foreign currency (USD) and local currency (PHP) proposals shall be evaluated using the benchmark conversion rate of **USD 1.00 = PHP 55.00**. For offshore active equipment (Lots 1, 2, 3, 7), contracts and Letters of Credit (LC) may be denominated directly in USD.
3. **Value Added Tax (VAT) Status:**

- All unit rates, material pricing, and services fees in Document 06 must be quoted **exclusive of 12% Philippine Value Added Tax (VAT-Exclusive)**. VAT will be added as a separate billing item pursuant to Bureau of Internal Revenue (BIR) regulations.

4. **Partial Lot Bidding & Custom Line Items:**
   - Bidders are fully permitted to bid on single Lots or arbitrary combinations of Lots (e.g. RAN only, Core only, Civil only). Non-quoted lots shall be marked 'NO BID'. Custom proprietary hardware or services may be included utilizing the designated custom line-item entry rows.
5. **Years 6–10 OPEX in 10-Year TCO:**
   - Bidders may structure Years 6–10 extended maintenance and managed services pricing as either fixed annual fees or transparent percentage-based annual escalations within Form C of Document 06.
6. **Mandatory OEM Technical Training:**
   - Turnkey proposals must include comprehensive OEM technical training and certification programs covering 5G SA Core administration, Band n50 RF planning/optimization, and OSS/BSS operations for at least twenty (20) TelTech technical personnel.

---

9. CONSOLIDATED RESPONSE MATRIX (PART 3: BIDDER CLARIFICATIONS Q045 – Q100 — BID BULLETIN NO. 2.1)

No.	Domain Classification	Document Reference	Prospective Bidder In
1 Q045	**Core network & IT infrastructure and delivery**	01_RFP_5G_FWA_Master_Tender_Document.pdf 1.2 ProgramLOT 3: CLOUD-NATIVE 5G CORE (5GC SA) & DATACENTER INFRASTRUCTURE	Please specify how mu million users in the firs throughput will be nee future.
2 Q046	**Wireless and Delivery**	07_RFP_5G_FWA_Candidate_Site_List_and_Rollout_Schedule.xlsx Phase 1 (First 1,000 Sites)	We have obtained the column T in the table c specific latitude and lo provide these tower's coordinates to support evaluation?

No.	Domain Classification	Document Reference	Prospective Bidder In
3 Q047	**Wireless and Delivery**	01_RFP_5G_FWA_Master_Tender_Document.pdf 2.1 Spectrum Physics: Band n50 Advantage	The current capability range of 1512~1517 MH Bidder requires more c conduct an evaluation. the NTC's demonstrati Contractor / Prospecti information: the suppr signals in the 1432~14 suppression level requ 1517 MHz.

No.	Domain Classification	Document Reference	Prospective Bidder In
4 Q048	CPE	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 7: 5G CUSTOMER PREMISES EQUIPMENT (CPE - LOT 7)	There is no ODU N50 p while for development indoor N50 first

No.	Domain Classification	Document Reference	Prospective Bidder In
5 Q049	OSS & BSS Integration	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	Is there an existing BI/I confirm if BSS doesn't anymore.
6 Q050	OSS & BSS Integration	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	Is there an existing cor separate customer tick
7 Q051	OSS & BSS Integration	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	How about VAS systen with existing SMS?
8 Q052	Site, civil work, and managed services	01_RFP_5G_FWA_Master_Tender_Document LOT 5: RF PLANNING, SITE SURVEY & CLUSTER OPTIMIZATION	We note your confirma is accepted. To align e following: (a) TSSR photographic panoramic photograph height from towerco. D TSSR. (b) The acceptance cr that they clearly depic environment (including potential obstructions, sufficient for line-of-si camera resolution, foc required; standard pho the site survey team is

No.	Domain Classification	Document Reference	Prospective Bidder In
9 Q053	Site, civil work, and managed services	05_Appendix_D_Site_Survey_RF_Planning_Civil_Power_Guidelines.pdf 4. CIVIL WORKS & STRUCTURAL ENGINEERING (CLASS T4 GREENFIELD SITES)	For 103 sites, Do we n foundation in the comr confirm the required h as VO.
10 Q054	Site, civil work, and managed services	03_Appendix_B_Commercial_Proposal_BoQ_Templates TABLE 3: LOT 2 — POWER SYSTEMS & PASSIVE INFRASTRUCTURE	1. Please suggest the r the Contractor / Prosp handover the site to Te 2. If Yes, When we han need to refuel the fuel
11 Q055	Site, civil work, and managed services	05_Appendix_D_Site_Survey_RF_Planning_Civil_Power_Guidelines.pdf 2.4 Backhaul Transmission Path Survey	Do we need to provide Starlink? If yes, please for the pole.
12 Q056	Site, civil work, and managed services	05_Appendix_D_Site_Survey_RF_Planning_Civil_Power_Guidelines.pdf 4. CIVIL WORKS & STRUCTURAL ENGINEERING (CLASS T4 GREENFIELD SITES)	Please suggest how m consider in the monop provide the dimension RRU、MW which need
13 Q057	Site, civil work, and managed services	05_Appendix_D_Site_Survey_RF_Planning_Civil_Power_Guidelines 03_Appendix_B_Commercial_Proposal_BoQ_Templates 2.3 Power Infrastructure & Utility Audit TABLE 3: LOT 2 — POWER SYSTEMS & PASSIVE INFRASTRUCTURE	For the New monopole capacity we need to ap

No.	Domain Classification	Document Reference	Prospective Bidder In
14 Q058	**OSS & BSS Integration**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	Regarding the CPE rec Contractor / Prospecti period allows for free r such a service accepta cannot be controlled.
15 Q059	**SLA&KPIs**	04_Appendix_C_SLAs_KPIs_Liquidated_Damages.pdf 3. RADIO ACCESS NETWORK (RAN) OPERATIONAL KPIS & SERVICE CREDITS	Regarding the MTTR、 Due to the lack of live inputs, it is impossible KPIs: SLA is recommended t actual values observed acceptance and comm
16 Q060	**Commercial Template**	06_RFP_Commercial_Price_Book_and_BoQ_Template All	The portal "3. Commer contents is different w "06_RFP_Commercial_ Kindly clarify which ve
17 Q061	**Commercial Template**	Portal "3. Commercial BoQ & Financing Lots 1-7" All	Regarding the vendor "3. Commercial BoQ & Since the current BOQ project, please clarify subsequent years: CAPEX: Assuming the exact pricing be applic 5? OPEX: Since vendors a Phase 1, how should w For Phase 2, do we mu Does this same logic a to Year 5?

No.	Domain Classification	Document Reference	Prospective Bidder In
18 Q062	**Commercial Template**	Portal "3. Commercial BoQ & Financing Lots 1-7" All	As the USD to PHP exc significantly right now, financial risk. We prop documents (BoQ, PO, you prefer to pay in PH exchange rate on the c
19 Q063	**Commercial Template**	Portal "3. Commercial BoQ & Financing Lots 1-7" All	Kindly clarify for Comm need to be filled online 1. If we are unable to p the bidder leave the ur 2. Where is the best pl assumptions?
20 Q064	**SLI**	01_RFP_5G_FWA_Master_Tender_Document LOT	1. Installation Scope & In which scenarios is ir Contractor / Prospecti installation? How to ca Dispatch Lead Time? 2. FTR Calculation: Ho Installation Rate calcul
21 Q065	**OSS & BSS Integration**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	Since it is a managed s accept the OSS tools c How to handle the tool
22 Q066	**SLA&KPIs**	04_Appendix_C_SLAs_KPIs_Liquidated_Damages 3.1 Core Radio KPIs (Calculated 24/7/365 Nationwide)	Service creadit penalty threshold mean Minim

No.	Domain Classification	Document Reference	Prospective Bidder In
23 Q067	SLA&KPIs	05_Appendix_C_SLAs_KPIs_Liquidated_Damages 3.1 Core Radio KPIs (Calculated 24/7/366 Nationwide)	kindly provide formula rate X erab assignmen
24 Q068	SLA&KPIs	06_Appendix_C_SLAs_KPIs_Liquidated_Damages 3.1 Core Radio KPIs (Calculated 24/7/367 Nationwide)	busy hour means auto such as 19:00- 20:00?
25 Q069	SLA&KPIs	07_Appendix_C_SLAs_KPIs_Liquidated_Damages 3.1 Core Radio KPIs (Calculated 24/7/368 Nationwide)	1. because there is " c this drive test KPI ? us throughput? 2. how to define cell ec
26 Q070	SLA&KPIs	5.7 Radio Frequency (RF) Cluster Optimization	the target of cluster op outdoor target , any ta throughput ?
27 Q071	SLA&KPIs	05_Appendix_D_Site_Survey_RF_Planning_Civil_Power_Guidelines.pdf 5.. SINGLE SITE VERIFICATION (SSV) & CLUSTER ACCEPTANCE CRITERIA	for Near , mid and far l simulation of typcial si and give proper distan RSRP level at -90, -10(
28 Q072	Wireless and Delivery	01_RFP_5G_FWA_Master_Tender_Document.pdf 2.1 Spectrum Physics: Band n50 Advantage	From our general unde allocation are usually u to know whether TelTe from the NTC to use 8 outside the NCR.

No.	Domain Classification	Document Reference	Prospective Bidder In
29 Q073	**Wireless and Delivery**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 1: RADIO ACCESS NETWORK (RAN) TECHNICAL SPECIFICATIONS	Antennas are generally positions on towers. To antenna's windward ar TelTech have requirem area and wind load cap Prospective Bidder's e base stations, it is reco area does not exceed
30 Q074	**Warranty**	01_RFP_5G_FWA_Master_Tender_Document.pdf	Please confirm that the Period (DLP / Hardwar equipment remains 24 of PAC issuance per si clarify whether the Ext Management Service (Years 6–10 for TCO ca separate, optional line B Commercial BoQ.
31 Q075	**Training**	01_RFP_5G_FWA_Master_Tender_Document.pdf	Please clarify whether and certification progr n50 RAN, BSS/OSS, ar TelTech's engineering kindly provide the esti preferred training loca Manila/Clark vs. OEM h should be quoted as a Commercial BoQ.
32 Q076	**Commercial Template**	Portal "3. Commercial BoQ & Financing Lots 1-7"	For the Years 6–10 Cu Services and Extended TCO evaluation, please to include an annual C inflation indexation and account for long-term
33 Q077	**Commercial Template**	Portal "3. Commercial BoQ & Financing Lots 1-7"	Are all unit prices in Co VAT Ex (Value Added T

No.	Domain Classification	Document Reference	Prospective Bidder In
34 Q078	**Power system and delivery**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 2: POWER SYSTEMS & PASSIVE SITE INFRASTRUCTURE	1. Does it requires 2 Re Configuration? For ex: 2. Do they need monit 3. Please confirm weat indoor or outdoor? 4. If outdoor installatio same set up?
35 Q079	**OSS & BSS Integration**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	In the FM app, is it acc function redirects to a Maps?
36 Q080	**OSS & BSS Integration**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	In the FM app, is the e handwritten signatures used for strong auther to be integrated. Curre
37 Q081	**OSS & BSS Integration**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	For RF signal verificati professional software s accurate and professio
38 Q082	**OSS & BSS Integration**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	Does the installation o
39 Q083	**Wireless and Delivery**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 5: RF PLANNING, SITE SURVEY & CLUSTER OPTIMIZATION	The areas covered by t mostly suburban or rur capability to use 5-me to using 2D maps entir

No.	Domain Classification	Document Reference	Prospective Bidder In
40 Q084	**Wireless and Delivery**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 1: RADIO ACCESS NETWORK (RAN) TECHNICAL SPECIFICATIONS	According to the curre maximum average traf exceed 1 Gbit/s. There support 2 x 10GE + 2 x recommended that onl reserved, that is, 2 x 2
41 Q085	**Wireless and Delivery**	07_RFP_5G_FWA_Candidate_Site_List_and_Rollout_Schedule.xlsx Phase 1 (First 1,000 Sites)	Considering there are advisable to use cabin
42 Q086	**OSS & BSS Integration**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	Regarding the CPE rec Contractor / Prospecti period allows for free r such a service accepta cannot be controlled.
43 Q087	**SLA&KPIs**	04_Appendix_C_SLAs_KPIs_Liquidated_Damages.pdf 3. RADIO ACCESS NETWORK (RAN) OPERATIONAL KPIS & SERVICE CREDITS	Regarding the MTTR、 Due to the lack of live inputs, it is impossible KPIs: SLA is recommended t actual values observed acceptance and comm
44 Q088	**SLI**	01_RFP_5G_FWA_Master_Tender_Document LOT	What is installation? In required? Is the Contra responsible for the ins New Installation Dispa

No.	Domain Classification	Document Reference	Prospective Bidder In
45 Q089	**SLI**	01_RFP_5G_FWA_Master_Tender_Document LOT	How is the First-Time- calculated?
46 Q090	**SLI**	01_RFP_5G_FWA_Master_Tender_Document LOT	Please provide the pro recovery, and mainten
47 Q091	**SLA&KPIs**	04_Appendix_C_SLAs_KPIs_Liquidated_Damages.pdf 3. RADIO ACCESS NETWORK (RAN) OPERATIONAL KPIS & SERVICE CREDITS	Does NBD in SPMS me Prospective Bidder's r
48 Q092	**OSS & BSS Integration**	02_Appendix_A_Technical_Specifications_Compliance_Matrix.xlsx SECTION 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION	Can the standalone OS decoupled from the fo Installation Dispatch L Installation Rate, and C Rate.

No.	Domain Classification	Document Reference	Prospective Bidder In
49 Q093	**Site, civil work, and managed services**	APPENDIX E: SERVICES STATEMENT OF WORK & MASTER RATE CARD 4. MASTER SERVICES PRICING SCHEDULE & COMMERCIAL RATE CARD	1. Please suggest on w tower retrofitting work to towerco to do retrof 2. Tower retrofitting ne first, and this scope ar case by case, Please s
50 Q094	**SLA&KPIs**	05_Appendix_C_SLAs_KPIs_Liquidated_Damages 3.1 Core Radio KPIs (Calculated 24/7/366 Nationwide)	Suggest CSSR target 9 based on huawei globa setup success rate 99 The CSSR further impr terminal compatibility coverage, and transmi
51 Q095	**SLA&KPIs**	05_Appendix_C_SLAs_KPIs_Liquidated_Damages 3.1 Core Radio KPIs (Calculated 24/7/366 Nationwide)	Suggest target 1.5%, The same reason that constrainted from term extent of network cove indoor CPE.
52 Q096	**SLA&KPIs**	05_Appendix_C_SLAs_KPIs_Liquidated_Damages 3.1 Core Radio KPIs (Calculated 24/7/366 Nationwide)	suggest to remove bot user behavior and user already reflected in SS
53 Q097	**SLA&KPIs**	05_Appendix_C_SLAs_KPIs_Liquidated_Damages 3.1 Core Radio KPIs (Calculated 24/7/366 Nationwide)	There is no OSS KPI la are available, which ha
54 Q098	**SLA&KPIs**	05_Appendix_C_SLAs_KPIs_Liquidated_Damages 3.1 Core Radio KPIs (Calculated 24/7/366 Nationwide)	suggest target 0.1%,
55 Q099	**Wireless and Delivery**	05_Appendix_D_Site_Survey_RF_Planning_Civil_Power_Guidelines.pdf 5.. SINGLE SITE VERIFICATION (SSV) & CLUSTER ACCEPTANCE CRITERIA	from last time clarifica SSV SPEED TARGETS - Near Zone (< 500m): Mbps.

No.	Domain Classification	Document Reference	Prospective Bidder In
			- Mid Zone (1.0 – 1.5 k Mbps. - Far / Cell Edge (>= 2. Mbps (minimum SLA tl Suggest to be : Slot configuration: DL: static test, >-80dBm: DL 200Mbp [-80~-95)dBm: DL 10([-95~-105)dBm: DL 3!
56 Q100	**Transmission**	01_RFP_5G_FWA_Master_Tender_Document 2.3 Transmission & Backhaul Topology	1, The SFP of Transmis with BBU will be provic Prospective Bidder or 2, The SFP of BBU will Module, the SFP of tra also, or specific ones a confirm the transmissi 3, The related configu for BBU integration wil Contractor / Prospecti

End of Bid Bulletin No. 2.1. Promulgated as an Official and Binding Addendum by the Special Bids and Awards Committee (SBAC) / Procurement Directorate on October 30, 2026.