

Telecommunications Technology Solutions Inc.
(TelTech)

Corporate Tender Secretariat · Procurement & Network Engineering Division

RFP-TELTECH-FWA-2026-001 /
MASTER

Author: OLIVER TUNGOL
Date: October 6, 2026

Turnkey 5G FWA Master Tender & RFP Specifications

Nationwide 5,000-Site Turnkey 5G Fixed Wireless Access (Band n50, 60 MHz TDD)

DOCUMENT NUMBER	AUTHOR	TARGET SPECTRUM	BIDDING STATUS
RFP-TELTECH-FWA-2026-001	OLIVER TUNGOL	Band n50 (1.5 GHz, 60 MHz TDD)	Official Request for Proposal

1. EXECUTIVE SUMMARY & INVITATION TO BID

1.1 Purpose of the Tender

Telecommunications Technology Solutions Incorporated (TelTech) (hereinafter referred to as the "Operator" or "Company") hereby invites qualified, world-class telecommunications equipment manufacturers, network systems integrators, and managed service providers (hereinafter referred to as the "Bidder" or "Vendor") to submit comprehensive, binding technical and commercial proposals for the turnkey supply, delivery, installation, integration, optimization, and managed operations of a nationwide **5G Fixed Wireless Access (FWA) Network**. The Operator is actively seeking creative, high-impact proposals—both technical and commercial—from prospective bidders that deliver industry-leading spectral efficiency, innovative vendor financing architectures, accelerated rollout velocity, and optimized Total Cost of Ownership (TCO).

The Operator has been officially awarded a Provisional Authority / Permit to Test and Demo Broadcast for **Band n50 (1432 – 1517 MHz, 1.5 GHz L-Band TDD)** with a **60 MHz contiguous carrier block**, and holds a pending application for the permanent commercial assignment and use of the said frequency band pursuant to and subject to the provisions of the Open Access in Data Transmission Act (**Konektadong Pinoy Law**) and National Telecommunications Commission (NTC) regulatory frameworks.

1.2 Program Scope & Deployment Scale

The nationwide program encompasses a total footprint of **5,000 macro BTS sites** deployed across five (5) consecutive phases:

- * **Phase 1 (Day-1 Priority Launch): 1,000 Macro Sites** (Batch 1 — immediate rollout across prioritized unserved and underserved suburban and rural population centers).
- * **Phases 2 to 5 (Nationwide Expansion): 1,000 Macro Sites per annum** over Years 2 through 5, reaching full target deployment of 5,000 BTS sites serving over **2.45 to 2.66 Million active broadband subscribers**.
- * **Target Addressable Population:** Over **32.3 Million residents** across 5,000 barangays (2024 PSA POPCEN Official Census baseline).
- * **Initial Network Sizing Load:** 1,000 active concurrent fixed broadband subscribers per 3-sector BTS (capacity ceiling of 5,965 peak BTS units across expansion).

1.3 Tender Structure & Bid Lots

Bidders are invited to submit tenders for one, multiple, or all of the following distinct Lots:

- * **LOT 1: Radio Access Network (RAN) Hardware, Antennas & Turnkey Deployment Services**
- * **LOT 2: Power Systems & Passive Site Infrastructure (Co-location Interconnect & Hybrid DC Power)**
- * **LOT 3: Cloud-Native 5G Core Network (5GC SA) & Datacenter Infrastructure**
- * **LOT 4: Converged Digital OSS/BSS, Field Force Automation & Real-Time Charging Engine**

- * **LOT 5: RF Planning, Greenfield Site Survey, Civil Works & Cluster Optimization Services**
- * **LOT 6: Nationwide Managed Services, 24/7 Tier-2/Tier-3 NOC & Field Network Operations (MS)**
- * **LOT 7: Customer Premises Equipment (CPE) 5G Sub-3 GHz High-Gain Terminals**

Bidders submitting integrated "Full Turnkey Consortium" bids spanning Lots 1 through 6 will receive multi-lot synergy evaluation scoring.

2. PROJECT BACKGROUND, OPERATING ENVIRONMENT & TECHNICAL BASELINE

2.1 Spectrum Physics: Band n50 Advantage

Band n50 operates in the 1.5 GHz L-Band (1432 – 1517 MHz), providing superior propagation characteristics over mid-band frequencies (e.g., 3.5 GHz Band n78):

- * **Propagation Efficiency:** 1.5 GHz propagation achieves an effective reliable non-line-of-sight (NLOS) and near-line-of-sight (nLOS) coverage radius of **3.5 km** (delivering up to **38.5 km²** of coverage area per site under suburban/rural clutter).
- * **Penetration Resilience:** Foliage, atmospheric rain fade, and typical Philippine residential building materials (concrete hollow block, corrugated galvanized sheet roofing) suffer 8–12 dB lower path loss compared to 3.5 GHz.
- * **Spectrum Allocation:** 60 MHz contiguous TDD frame structure (configurable TDD DL:UL ratios: 4:1 for broadband downlink-heavy traffic, or 3:1 for balanced enterprise transmission).

2.2 Site Infrastructure Landscape & Tower Strategy

The operator has completed a nationwide spatial overlay matching the 5,000 candidate barangay centroids against **13,746 verified operational cell towers** spanning six (6) tower portfolios:

- * **PTCI / MIDC TowerCo:** 5,080 towers
- * **FTAP Globe Telecom:** 3,529 towers
- * **EdgePoint Infrastructure:** 2,775 towers
- * **FTAP Smart Communications:** 1,023 towers
- * **LBS Digital Infrastructure (LDIC):** 700 towers
- * **FTAP BTS Dedicated Sites:** 639 towers

Deployment Typology (Co-location vs. Greenfield):

- **Class T1 (Immediate Co-location, <= 0.5 km):** 54.8% of Phase 1 sites (42.5% nationwide). Sited directly on operational TowerCo structures with existing AC power and civil compound.
- **Class T2 (Close Co-location, 0.5 - 1.0 km):** 26.9% of Phase 1 sites (30.4% nationwide). Sited on operational towers within beamforming reach.
- **Class T3 (Near Co-location, 1.0 - 2.0 km):** 8.0% of Phase 1 sites (17.8% nationwide). Co-location viable subject to RF propagation clearance.
- **Class T4 (Greenfield Monopole Required, > 2.0 km):** 10.3% of Phase 1 sites (9.3% nationwide; ~460 sites total). Requires self-constructed 30m/40m monopole, civil shelter, dedicated utility transformer drop, and backup diesel/solar generation.

2.3 Transmission & Backhaul Topology

Transmission connectivity has been audited via the Converge fiber network audit (1,296 confirmed optical nodes and 4,401 fiber segments; subject to verification on the ground):

- * **Terrestrial Fiber Optic Cable (FOC):** 98.3% of Phase 1 sites connect via terrestrial fiber drops (Class A: Node <= 0.5 km; Class B: Node <= 1.0 km; Class C: Line-tap splice closure <= 0.5 km; Class D: Lateral/Microwave <= 3.0 km).
 - * **Satellite LEO Backhaul (Starlink Business):** 1.7% of Commercial Phase 1 sites (and up to 34.4%–43.5% in remote universal access/GIDA sites) utilize 4-terminal Starlink Business arrays (delivering aggregated 400–800 Mbps burst with SD-WAN bonding and traffic shaping).
-

3. SCOPE OF WORK BY TENDER LOT

LOT 1: 5G RAN EQUIPMENT & ACCESS HARDWARE

The Bidder shall supply, deliver, install, test, and commission carrier-grade 3GPP Release 16/17 compliant 5G RAN equipment:

1. Baseband Unit (BBU):

- * High-capacity rack-mountable 19" subrack BBU supporting multi-cell aggregation and up to 12 cells of 60 MHz Band n50.
- * Dual redundant DC power supply inputs (-48V DC, operating range -40.5V to -57V DC).
- * Backhaul interfaces: Minimum 4x 10GE/25GE optical SFP28 interfaces supporting IEEE 1588v2 Precision Time Protocol (PTP) Telecom Profile (G.8275.1) and SyncE.
- * Fronthaul interfaces: Minimum 6x 25GE eCPRI interfaces with integrated Optical Supervisory Channel (OSC).

2. Remote Radio Units (RRU) / Active Antenna Units (AAU):

- * Configuration: **8T8R MIMO**, 3 sectors per macro site (total of 3 RRUs and 3 antennas per standard macro).
- * Operating Frequency: Band n50 (1432 – 1517 MHz), full 60 MHz IBW (Instantaneous Bandwidth) and OBW (Occupied Bandwidth).
- * RF Output Power: Minimum **8 x 40W (320 W total RF power per sector)**.
- * Beamforming capability: Digital horizontal and vertical beamforming supporting dynamic multi-user MIMO (MU-MIMO) pairing.
- * Protection & Environment: IP65/IP67 ingress rating, natural convection or high-durability fanless cooling, surviving wind speeds of up to 250 km/h (Typhoon Category 5 resilience).

3. Macro Antennas & RF Ancillaries:

- * High-gain 8-port cross-polarized antennas (or integrated AAU) supporting Band n50 with electrical remote downtilt (eRET via AISG 2.0 / 3GPP).
- * Horizontal half-power beamwidth: 65° +/- 5°; Minimum gain ≥ 17.5 dBi.
- * Low PIM performance: ≤ -153 dBc @ 2 x 43 dBm.
- * High-grade low-loss optical fiber patchcords, IP67 weatherproof boot assemblies, DC power surge protective devices (SPD Type 1+2), and grounding kits.

LOT 2: POWER SYSTEMS & PASSIVE INFRASTRUCTURE

The Bidder shall provide unified site power solutions engineered for high availability across both leased TowerCo sites and greenfield sites:

1. DC Power Rectifier Plant:

- * Modular 19" 3U/4U switchmode DC power system dimensioned for **6.0 kW** continuous capacity (4 x 2.0 kW or 3 x 3.0 kW hot-swappable rectifier modules in N+1 redundancy).
- * Rectifier efficiency: $\geq 96.0\%$ (80 PLUS Titanium / high-efficiency class).
- * Advanced SMPS controller with SNMPv3, HTTPS, Modbus, dry contacts, and remote cloud telemetry.

2. Battery Energy Storage System (BESS):

- * Lithium Iron Phosphate (LiFePO4 / LFP) battery modules: Minimum **1 x 48V / 150 Ah (or 2 x 100 Ah)** providing ≥ 4 hours backup autonomy at standard 2.5–3.0 kW BTS operational load.
- * Cycle life: $\geq 4,000$ cycles at 80% Depth of Discharge (DoD) @ 25°C.
- * Built-in intelligent BMS with cell-level balancing, over-charge, over-discharge, short-circuit, and high-temperature thermal runaway cutoffs.

3. Standby Generator Sets (Greenfield Class T4 Sites):

- * 15 kVA / 12 kW prime-rated, 230V single-phase / 400V 3-phase, 60 Hz water-cooled diesel generator with sound-attenuated weatherproof enclosure (< 68 dBA @ 7m).
- * Minimum 500-liter to 1,000-liter sub-base day fuel tank providing ≥ 72 hours continuous operation during grid blackout.
- * Automatic Transfer Switch (ATS) with motorized 4-pole contactor and mechanical interlock.

4. TowerCo Co-Location Power Interconnect Kit:

- * Standardized DC tap-off distribution box, sub-metering Class 1.0 revenue-grade energy meter with RS485 telemetry, and dedicated surge suppression.

LOT 3: CLOUD-NATIVE 5G CORE (5GC SA) & DATACENTER INFRASTRUCTURE

The Bidder shall deploy a carrier-grade, cloud-native 5G Standalone (5G SA) Core Network dimensioned for **1,000,000 initial registered subscribers** scaling up to **3,000,000 subscribers**, deployed in a **Geo-Redundant, Active-Active Dual Datacenter Topology** (NCR Primary DC and Metro Clark / Region III Disaster Recovery DC):

1. Network Functions (NFs) Scope:

- * Control Plane: AMF, SMF, NRF, NSSF, PCF, UDM, UDR, AUSF, NEF, CHF.
- * User Plane: High-performance distributed User Plane Function (UPF) nodes.

2. User Plane (UPF) Throughput Dimensioning:

- * UPF capacity dimensioned for **80 Gbps usable throughput per 2U dual-socket compute node** (minimum 2 x 100GE line-rate DPDK / SR-IOV interfaces).
- * Integrated high-performance **Carrier-Grade NAT (CG-NAT)** supporting deterministic port allocation and 10:1 to 16:1 subscriber port density.
- * Integrated Deep Packet Inspection (DPI) for layer-7 traffic classification, fair-use bandwidth throttling, and URL filtering.

3. Hardware & CaaS Virtualization Infrastructure:

- * Enterprise OpenStack or Bare-Metal Kubernetes (CaaS) orchestration platform.
- * Dual-socket Intel Xeon / AMD EPYC server nodes, 512 GB RAM, dual 25G/100G NICs, redundant enterprise NVMe storage arrays.
- * Redundant datacenter leaf-spine fabric switches (32 x 100GE spine, 48 x 25GE + 6 x 100GE leaf), redundant perimeter next-gen firewalls, and DDoS mitigation scrubbing appliances.

4. Licensing Framework:

- * Tiered perpetual subscriber capacity licensing:
- * Tier 1 (First 100k subs): Bidder to quote per registered sub.
- * Tier 2 (100k to 500k subs): Bidder to quote per registered sub.
- * Tier 3 (500k to 1M+ subs): Bidder to quote per registered sub.

LOT 4: CONVERGED DIGITAL OSS/BSS & FIELD FORCE AUTOMATION

The Bidder shall deliver an integrated, cloud-native Telecom Business Support System (BSS) and Operations Support System (OSS) optimized for high-volume, low-friction fixed broadband operations:

1. Converged BSS & Omnichannel Customer Engagement:

- * Omnichannel CRM, Product Catalog, and CPQ supporting 4 primary retail tariffs and SME tiers.
- * Native Prepaid-First architecture: Integration directly with 5G Core Charging Function (CHF) via 3GPP Nchf / Diameter Ro interfaces.
- * Payment Gateway Integrations: Native, production-ready REST API integrations with Philippine digital payment channels: **GCash, Maya (PayMaya), 7-Eleven CLiQQ OTC, Bayad Center**, bank transfer (InstaPay/PESONet), and municipal distributor airtime portals.

2. Field Force Management (FMS) & Mobile Technician App:

- * Automated work-order generation and algorithmic dispatch engine handling up to **3,500 daily work orders** (new installs, truck rolls, relocations, CPE reclaims, and trouble calls).
- * Android mobile app for field technicians: Real-time GPS dispatch, barcode/QR scanning of CPE MAC and serial numbers, automated outdoor signal sweep tool (RSRP/SINR validation), photograph proof of installation, and customer digital e-signature.
- * Turnaround SLA: Compressed installation timeline from 14 calendar days down to **under 48 hours** from order booking.

3. CPE Warehouse Logistics & Asset Reverse Logistics (WMS):

- * End-to-end serialized asset tracking from central warehouse staging through regional depots, technician truck float, subscriber premises, and repossession/refurbishment cycle.
- * Support for minimum 70% CPE recovery and refurbishment upon subscriber churn.

4. OSS Network Management, Fault & Performance Monitoring:

- * Multi-vendor RAN EMS/NMS integration via 3GPP northbound REST/Kafka/SNMP interfaces.
- * Real-time automated fault correlation, root-cause analysis (RCA), and synthetic SLA monitoring.
- * Automated NTC regulatory compliance KPI dashboard and QoS reporting engine.

LOT 5: RF PLANNING, SITE SURVEY & CLUSTER OPTIMIZATION

The Bidder shall execute end-to-end RF planning, site survey, civil design, and cluster radio tuning:

1. Detailed Greenfield & Co-Location Site Surveys:

- * Technical Site Survey Report (TSSR) for each assigned candidate barangay: Detailed structural load analysis on existing towers, antenna mounting space, azimuthal line-of-sight (LOS) drone photographic sweeps (360° at 20m, 30m, 40m AGL), AC power distribution panel capacity, grounding resistance (≤ 5 Ohms), and backhaul cable routing.

2. High-Precision RF Propagation Modeling:

- * Production-grade RF propagation model tuning in Asset / Atoll / Planet utilizing high-resolution GIS clutter and 3D digital elevation models (DEM ≤ 5 m resolution).
- * Cell dimensioning: Sizing for 60 MHz Band n50 TDD, 3 sectors @ 120° nominal separation, antenna height 30m–45m AGL, coverage target RSRP ≥ -95 dBm across $\geq 90\%$ of populated barangay settlement areas.

3. Single Site Verification (SSV) & Cluster Tuning:

- * SSV drive tests and stationary multi-point testing per site verifying 3-sector RF radiation, antenna tilt (RET), PCI validation, azimuth verification, and handover execution.
- * Cluster optimization across 10–20 site clusters to eliminate pilot pollution, optimize neighbor lists, minimize inter-cell interference, and balance sector traffic loading.

LOT 6: NATIONWIDE MANAGED SERVICES & 24/7 NETWORK OPERATIONS (MS)

The Bidder shall provide fully managed, SLA-governed network operations, field maintenance, and spare parts management:

1. Tier-2 & Tier-3 Network Operations Center (NOC):

- * 24/7/365 active monitoring of RAN, Core, Transmission, Power, and OSS/BSS platforms.
- * Incident management, event correlation, dispatching field maintenance teams, and managing customer trouble ticket escalations.

2. Nationwide First-Line Maintenance (FLM) Field Operations:

- * Regional field maintenance hubs across Greater Luzon, Northern Luzon, Southern Luzon, Visayas, and Mindanao.
- * Mean Time to Respond (MTTR) ≤ 2 hours in urban/suburban and ≤ 4 hours in rural clusters for Critical/Severity-1 incidents.
- * Preventive maintenance: Quarterly inspection of RF antenna brackets, coax/optical jumpers, rectifier modules, battery conductance testing, and generator load testing.

3. Comprehensive Spare Parts Management (SPMS):

- * Advanced replacement logistics: Central warehouse and regional staging depots maintaining an audited safety float of BBUs, RRUs, rectifiers, lithium batteries, and SFPs.
- * Guarantee of next-business-day (NBD) on-site replacement delivery for failed hardware components.

LOT 7: 5G HIGH-GAIN CUSTOMER PREMISES EQUIPMENT (CPE)

The Bidder shall supply outdoor and high-gain indoor 5G FWA CPE devices:

1. RF & Modem Specifications:

- * Chipset: 3GPP Release 16 compliant 5G NR sub-3 GHz processor.
- * Frequency Bands: Native Band n50 support (1432 – 1517 MHz, 60 MHz channel bandwidth) plus fallback sub-6 GHz bands (n1, n3, n7, n28, n41, n77, n78).
- * Antenna: Internal high-gain directional/omnidirectional antenna array (≥ 8 to 10 dBi antenna gain in Band n50); optional external TS-9/SMA antenna ports.
- * MIMO: 4R MIMO receiver architecture in Band n50 downlink.

2. LAN & Local Wi-Fi Specifications:

- * Wi-Fi 6 (802.11ax), dual-band 2.4 GHz + 5.0 GHz, 2 x 2 MU-MIMO, aggregate speed ≥ 1800 Mbps (AX1800).
- * Ethernet: Minimum 1 x 2.5GE + 2 x 1GE RJ-45 LAN ports.
- * Voice: 1 x FXS RJ-11 VoIP port (optional).

3. Device Management & TR-069 / USP (TR-369):

- * Full remote provisioning via TR-069 / TR-181 or TR-369 USP; remote firmware OTA (FOTA) upgrades; SIM-lock and network-lock enforcement tied to Operator PLMN (515-XX).

4. RIGOROUS SERVICE LEVEL AGREEMENTS (SLAs) & PERFORMANCE KPIS

The Bidder must guarantee compliance with the following international telecom best-practice KPIS. Failure to achieve these targets shall trigger contractual liquidated damages (LDs) and service credits.

4.1 Radio Access Network (RAN) Performance KPIS

KPI METRIC	FORMULA / STANDARD	MINIMUM ACCEPTANCE	TARGET EXCELLENCE	MEASUREMENT WINDOW
Radio Network Availability	$[(\text{Total Available Cell Hours} - \text{Cell Outage Hours}) / \text{Total Available Cell Hours}] \times 100\%$	$\geq 99.70\%$	$\geq 99.95\%$	Monthly / 24x7
5G Radio Accessibility (CSSR)	Call/Session Setup Success Rate (RRC + 5G QoS Flow)	$\geq 99.00\%$	$\geq 99.60\%$	Busy Hour
5G Session Drop Rate (CDDR)	Abnormal Release Rate per 100 established sessions	$\leq 0.50\%$	$\leq 0.15\%$	Busy Hour
Single Sector User Capacity	Active concurrent connected CPE sessions per sector	≥ 350 CPEs	≥ 450 CPEs	Peak Busy Hour
Peak Cell DL Throughput (60 MHz)	8T8R 60 MHz TDD peak aggregated sector throughput	≥ 450 Mbps	≥ 520 Mbps	Lab & Single Cell Test
Cell Edge DL User Throughput	95th percentile cell-edge subscriber download rate	≥ 25 Mbps	≥ 50 Mbps	Busy Hour
Cell Edge UL User Throughput	95th percentile cell-edge subscriber upload rate	≥ 5 Mbps	≥ 15 Mbps	Busy Hour
End-to-End User Latency (RTT)	CPE to UPF packet round-trip time	≤ 30 ms	≤ 18 ms	Continuous Ping
DL Packet Loss Rate (PLR)	User Plane packet discard rate	$\leq 0.10\%$	$\leq 0.01\%$	Monthly Average

4.2 Power & Site Infrastructure Resilience KPIS

INFRASTRUCTURE METRIC	TECHNICAL REQUIREMENT	MINIMUM SLA TARGET	FAILURE REMEDY
Site Power Availability	BTS Continuous Operating Power (AC Grid + DC Battery + Genset)	$\geq 99.95\%$ (Leased) $\geq 99.85\%$ (Greenfield)	Service credit deduction per hour outage
Battery Autonomy Duration	Time BTS operates on LFP battery during AC utility blackouts	≥ 4.0 Hours @ 3.0 kW load	Mandatory module replacement if < 3.5 hrs
Generator Auto-Start Reliability	Genset starts and ATS transfers load within 60s of grid failure	$\geq 99.0\%$ successful transfers	Liquidated damages on site drop
Grounding Earthing Resistance	Earth ground electrode resistance to true earth	≤ 5.0 Ohms	Mandatory soil conditioning / additional rods
Rectifier System Efficiency	Operating efficiency from 30% to 90% load range	$\geq 96.0\%$	Rejection of non-compliant modules

4.3 5G Core Network & Cloud Infrastructure KPIS

CORE METRIC	OPERATIONAL DEFINITION	TARGET SLA BENCHMARK
5GC Control Plane Availability	High availability of AMF, SMF, UDM, PCF across geo-cluster	$\geq 99.999\%$ ("Five Nines")
5GC User Plane Availability	Availability of UPF packet routing instances	$\geq 99.999\%$
PDU Session Establishment Success	Initial PDU session setup success rate	$\geq 99.80\%$

CORE METRIC	OPERATIONAL DEFINITION	TARGET SLA BENCHMARK
Session Setup Delay	End-to-end signaling time to establish 5G session	<= 80 ms (95th percentile)
UPF Packet Forwarding Latency	Processing delay through UPF hardware	<= 1.0 ms
CG-NAT Port Allocation Success	Real-time port assignment for new outbound sessions	>= 99.99%
Core Failover Recovery Time (DR)	Automatic cutover from NCR DC to Clark DR DC	<= 30seconds (Zero session loss)

4.4 OSS/BSS, Field Operations & Managed Services SLAs

OPERATIONAL SERVICE DOMAIN	METRIC DESCRIPTION	MANDATORY SLA BENCHMARK
BSS Billing & Rating System Availability	Online Charging System (CHF/OCS) uptime	>= 99.99%
Payment Top-Up Processing Time	Time from payment channel confirmation to account credit	<= 3seconds
Field Force Installation Lead Time	Order placement to physical CPE on-site activation	<= 48 Hours (Standard urban/suburban)
First-Time Right (FTR) Installs	Installations operating without trouble call within 14 days	>= 96.0%
Customer Churn CPE Recovery Rate	Successful physical recovery of CPE on churned accounts	>= 70.0%
Severity 1 Incident MTTR (Critical Outage)	Time to restore full service on macro BTS outage	<= 2 Hours (Urban) / <= 4 Hours (Rural)
Severity 2 Incident MTTR (Major Degraded)	Time to restore single sector failure or degraded backhaul	<= 6 Hours
Hardware Replacement Turnaround	Depot dispatch of spare BBU/RRU/Rectifier to site	<= 24 Hours (Nationwide NBD)

5. TENDER SUBMISSION STRUCTURE & COMPLIANCE REQUIREMENTS

Bidders must submit their proposals divided strictly into three (3) separate volumes:

Volume I: Executive & Commercial Proposal (Financial Envelope)

- Form A — Bid Submission Letter & Consortium Structure:** Executed by authorized corporate officers.
- Form B — Bill of Quantities (BoQ) & Unit Price Book:** Exhaustive pricing matrix in USD and PHP for all hardware, software licenses, implementation services, and annual maintenance contracts (AMC), completed using the official blank Excel BoQ template.
- Form C — Total Cost of Ownership (TCO) Breakdown (10-Year Horizon):** Itemized Day-1 CAPEX, expansion CAPEX, and 10-year OPEX schedules.
- Form D — Vendor Financing Proposal (Mandatory Requirement):**
- The Bidder **must** provide a detailed vendor financing facility covering at least **80% of Capex** (BTS hardware, core, and turnkey rollout).
- Tenor: Minimum 4-year to 5-year repayment facility.
- Interest Rate: Fixed commercial rate benchmarked to SOFR + spread.
- Grace Period: Minimum 12-month grace period on principal repayment during Phase 1 deployment.

Volume II: Technical Architecture & Compliance Matrix (Technical Envelope)

- Section A — RAN Technical Design:** 3GPP R16/17 compliance, Band n50 8T8R AAU/RRU datasheets, BBU subrack capacity, antenna radiation patterns, and link budget calculations.

2. **Section B — Power & Site Civil Engineering:** Rectifier plant, LFP battery cycle curves, genset specifications, and TowerCo co-location interface diagrams.
3. **Section C — 5G Core Architecture:** Cloud-native microservices architecture, dual datacenter active-active geo-redundancy topology, UPF DPDK hardware dimensioning, and CG-NAT sizing.
4. **Section D — OSS/BSS & IT Stack:** Modular architecture, digital self-care portal, payment channel API integrations, field-force management mobile application, and WMS inventory tracking.
5. **Section E — RF Planning & Cluster Optimization Methodology:** Link budget models, clutter definitions, drive-test methodology, and SSV acceptance criteria.
6. **Section F — Managed Services & Operations Plan:** NOC structure, FLM staffing model, SLA penalty framework, and spare parts dimensioning model.
7. **Compliance Matrix:** Line-by-line statement of compliance (**Compliant / Minor Deviation / Non-Compliant**) against every technical requirement in Appendix A.

Volume III: Bidder Qualifications, References & Financial Soundness

1. **Corporate Financial Statements:** Audited financial statements for the past three (3) fiscal years demonstrating solvency, liquidity, and operational turnover.
2. **Telecom Track Record:** Proof of at least three (3) commercial 5G deployments (RAN or Core) of similar or larger scale within the past 36 months.
3. **Philippine In-Country Support Structure:** Documented local Philippine engineering entity, SEC registration, local repair center, and existing field logistics capabilities.

6. BID EVALUATION CRITERIA & AWARD METHODOLOGY

Tenders will be evaluated using a **Quality and Cost-Based Selection (QCBS)** scoring framework:

$$\text{Total Evaluation Score} = (\text{Technical Score} \times 60\%) + (\text{Commercial \& Financing Score} \times 40\%)$$

6.1 Technical Evaluation Breakdown (100 Points / 60% Total Weight)

- **RAN Architecture & Radio RF Performance (25 Points):** Band n50 output power, 8T8R beamforming algorithms, power consumption efficiency, and environmental durability.
- **5G Core Architecture & Geo-Redundancy (20 Points):** Cloud-native architecture, UPF line-rate throughput, CG-NAT scale, and seamless hitless failover.
- **OSS/BSS Capabilities & Local Integrations (15 Points):** Real-time charging, native Philippine digital payment interfaces, automated field dispatch tool, and WMS inventory reverse logistics.
- **Power Engineering & Site Solution (10 Points):** LFP battery cycle life, rectifier efficiency, TowerCo co-location integration simplicity, and genset reliability.
- **RF Planning, Optimization & Rollout Methodology (15 Points):** Link budget precision, cluster tuning rigor, and proven ability to mobilize 1,000 sites in 12 months.
- **Bidder Experience, References & Local Entity (15 Points):** Tier-1 telecom reference base, local Philippine support team, and spare parts warehouse infrastructure.

6.2 Commercial & Financing Evaluation Breakdown (100 Points / 40% Total Weight)

- **Capex Competitiveness (40 Points):** Evaluated across lowest compliant Capex bids. Lowest qualifying responsive Capex receives full points.
- **10-Year Opex & TCO Efficiency (25 Points):** Low ongoing power consumption, competitive software AMC rates, and managed services unit pricing.

- **Vendor Financing Structure (35 Points):** Grace period length, interest rate spread, financing quantum ($\geq 80\%$), and ease of financial covenants.

7. TENDER TIMELINE & KEY MILESTONES

MILESTONE EVENT	SCHEDULED DATE	RESPONSIBILITY
Official RFP Tender Issuance	October 6, 2026	Operator Tender Committee
Bidder Registration & NDA Signing	October 16, 2026	Prospective Bidders
Pre-Bid Clarification Meeting (Hybrid)	October 23, 2026	Operator & Bidders
Deadline for Written Inquiries / RFIs	October 30, 2026	Prospective Bidders
Operator Formal Addendum & Clarifications	November 6, 2026	Operator Tender Committee
Tender Submission Deadline (Sealed Bids)	November 27, 2026 (17:00 PHT)	Bidders
Opening of Technical Envelopes	November 30, 2026	Operator Technical Board
Technical Clarifications & Vendor Presentations	December 1 – 11, 2026	Shortlisted Bidders
Opening of Commercial & Financing Envelopes	December 15, 2026	Operator Commercial Board
Final Contract Negotiation & Award	January 15, 2027	Operator & Winning Bidder(s)
Phase 1 Contract Execution & Kickoff	February 1, 2027	Operator & Appointed Contractor
Phase 1 Target Commercial Launch (1,000 Sites)	Q4 2027 (Within 12 Months)	Joint Deployment Team

8. INSTRUCTIONS TO BIDDERS & SUBMISSION DETAILS

8.1 Clarifications and Communications

All formal communications, requests for interpretation, and tender queries must be submitted in writing via official email to:

* **Tender Secretariat:** oliver.tungol@comclark.com.ph

* **Attention:** Technical Evaluation Board / OLIVER TUNGOL (Author)

* **Subject Line:** [RFP-TELTECH-FWA-2026-001] Technical Clarification Request – <Bidder Name>

8.2 Submission Format

- **Electronic Submission:** One (1) encrypted USB storage device containing PDF and editable Excel files of all volumes, plus cloud upload to the secure Operator Tender Portal.
- **Physical Submission:** Two (2) complete hard-copy sets (One Original, One Duplicate) of Volume I, Volume II, and Volume III, sealed in wax-stamped envelopes delivered to:
- *Tender Committee, Telecommunications Technology Solutions Incorporated (TelTech) Corporate Headquarters, Metro Manila, Philippines.*

(End of Request for Proposal Specification — Tender Appendices Follow)